

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hodgeman County, Sec. 21 Twp. 22S Rge. 26 (W)

Location as "NE/CNW/SW" or footage from lines SE/1 SW/1 SE/1

Lease Owner Iron Drilling Co.

Lease Name Irma Brack Well No. 1

Office Address 1206 Philtower Bldg., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-12/58 19

Application for plugging filed " 19

Application for plugging approved " 19

Plugging commenced " 19

Plugging completed " 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4680 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner		3852		8-5/8	618	None
Lansing		3894				
Base of Kansas City			4335			
Marmaton		4345				
Cherokee		4461				
Mississippi		4574				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled Hole with heavy mud to 550'. Set Wood Plug.

Set Cement plug on top of wood plug using 20 sacks of Cement.

Spotted cement plug through Drill Pipe.

Filled Hole with heavy mud to 35'. Set Wood Plug & Cemented with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Iron Drilling Company

Address 1206 Philtower Bldg., Tulsa, Okla.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
J. L. Stackpole (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. L. Stackpole
Tulsa, Okla. (Address)

SUBSCRIBED AND SWORN to before me this 2nd day of December

My commission expires Feb. 28, 1960

DEC 5 - 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 21 T. 22 R. 26W
BOOK PAGE 149 LINE 9

DRILLING RECORD

15-083-00099-0000

Irma Brack No. 1
SE/4 SW/4 SE/4 Sec. 21-22S-26W
Hodgeman County, Kansas

618' - 8-5/8" OD Casing
cemented w/ 350 sacks

Work Commenced: 10/24/58
Drilling Commenced: 10/25/58
Drilling Completed: 11/11/58
Work Completed: 11/12/58

No Oil String - Dry Hole

WELL LOG

Clay & Shale	0 - 255
Sand & Shale	255 - 570
Shale	570 - 755
Red Bed	755 - 1085
Shale & Lime	1085 - 1175
Sand - Red Bed	1175 - 1435
Red Bed & Shale	1435 - 1660
Gyp & Shale	1660 - 1745
Shale	1745 - 1895
Shale & Lime	1895 - 2615
Lime	2615 - 2680
Lime & Shale	2680 - 2815
Lime	2815 - 3053
Shale & Lime Stks	3053 - 3110
Lime & Shale	3110 - 3195
Lime	3195 - 3245
Shale	3245 - 3315
Shale & Lime	3315 - 3530
Lime	3530 - 3845
Lime & Shale	3845 - 3882
Lime	3882 - 4515
Lime & Shale	4515 - 4550
Conglomerate	4550 - 4560
Lime & Chert Congl	4560 - 4576
Cherty Lime	4576 - 4580
Chert	4580 - 4597
Lime & Chert	4597 - 4607
Lime	4607 - 4626
Lime & Shale	4626 - 4667
Lime & Chert	4667 - 4680 TD

CERTIFICATION

State of Oklahoma, County of Tulsa, SS

I, J. L. Stackpole, Employee of Iron Drilling Company, certify that the accompanying is a true and correct log of the above described well.

J. L. Stackpole

Subscribed to and Sworn before me this 2nd day of December, 1958

B. M. McElvaine
Notary Public

My Commission expires Feb. 28, 1960

PLUGGING
FILE SEC. 21 T. 22 R. 26W
BOOK PAGE 149 LINE 9

DEC 5 - 1958
CONSERVATION DIVISION
Wichita, Kansas