

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67702

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-10134-00-01

Lease Name Hallett Waterflood

WELL NUMBER Larkin #2 WIW

1650 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 15 TWP. 22S RGE. 25W (E) or (W)

COUNTY Hodgeman

Date well completed 1/31/57

Plugging Commenced 9/22/99

Plugging completed 9/22/99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Herman L. Loeb

Address P. O. Box 524 Lawrenceville, IL 62439

Phone (618) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well Input

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/21/99 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, IS well log attached? no

Producing Formation Spengen Warsaw Depth to Top 4592' Bottom 4648' T.D. 5210'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Spengen Warsaw</u>	<u>oil</u>	<u>4592</u>	<u>4648</u>	<u>8 5/8"</u>	<u>475'</u>	<u>0'</u>
				<u>4 1/2"</u>	<u>4709'</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Parted tubing with packer left in the hole, top of tubing @ 2403', packer @ 4650'. RIH w/ tubing to 2360', pump 50 sk cement w/ 200# of hulls

displace w/ 7 bbl water to balance plug (1760' to 2350'). Pull tubing up to 1700', pump 135 sk cement (0' to 1700'). Cement circulated.

POH w/ tubing. Top off w/ 25 sk cement. Hook on to surface casing, pump 30 sk cement down 5 1/2" x 8 5/8" annul us.

Use 60/40 poz mix w/ 6% gel.

Name of Plugging Contractor Cheyenne Well Service License No. 6454

Address P O Box 384 Ness City, KS 67560-0384

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb

STATE OF Illinois COUNTY OF Lawrence '33.

George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God.

(Signature) George A. Payne

(Address) 7588 Marywood Drive Newburgh, IN 47630

Subscribed and sworn to before me this 12th day of October, 19 99


RECEIVED

My STATE CORPORATION COMMISSION expires: April 6, 2002

OCT 12 1999

CONSERVATION DIVISION
Wichita, Kansas

10-12-99



Form CP-4

R.