


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 N. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 8 Twp. 22 Rge. 12 (E) W(W)

Location as "NE/CNW%SW%" or footage from lines 6 E/2 NW/4
Lease Owner Drillers & Producers Pipe & Supply.
Lease Name Charles #3 Well No. _____
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6-11-58 _____ 19____
Plugging completed 6-19-58 _____ 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3676' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	286'	none
				5-1/2"	3675'	2608'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 3676' and found it open.
Ran 5 sacks of cement on bottom. Pulled 5 1/2" casing, cleared hole and mudded the hole to 250', set a rock bridge to 240' and ran 12 sacks of cement. Checked top of cement to 210', bailed hole dry and ran 8 more sacks of cement. Mudded the hole to 35', set a rock bridge to 30' and ran 10 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
I, NOEL J. KNIGHT (employee of owner) or Notary Public of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Chase, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 19 58

Thomas V. Duggin
Notary Public.

My commission expires 9-27-58

STATE CORPORATION COMMISSION

JUN 27 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUG G
FILE SEC 8 T 22 R 12
BOOK PAGE 107 LI E 27

WELL RECORD

CHARLES NO. 3

Drillern pipe and Supply Producers Supply

KS-7781

~~50 ft. North of Center E/2 NW/4 of 8-22S-12W,~~
Stafford County, Kansas

DRACH POOL

State test 2-21-51 - Potential 80 BOPD.

Casing Record

280' of 8-5/8" 22.70# Armco Elec. Weld Casing set at 286' w/300 sax cement and 300# calcium chloride.

3680' of 5 1/2" OD 14# J-55 Pittsburgh seamless casing set at 3675 RKB w/150 sax cement.

FORMATION RECORD

<u>FORMATION</u>	<u>TOP</u>	<u>BOTTOM</u>
Sand & gravel	0	40
Sand	40	220
Red bed	220	286
Shale	286	385
Red bed & shells	385	675
Anhydrite	675	705
Shale & shells	705	1130
Salt, shale & shells	1130	1470
Shale & shells	1470	1515
Lime & shale	1515	1580
Shale & lime	1580	1705
Lime & shale	1705	1995
Shale & lime	1995	2030
Shale & shells	2030	2675
Shale & lime	2675	2825
Lime & shale	2825	2890
Lime	2890	3625
Shale & chert	3625	3645
Cherty shale	3645	3672
Arbuckle lime	3672	3676 TD

PRODUCING AREA: 3675-3676 (Arbuckle)

H Copies of Plugging report to Atlantic

PLUGGING
WELL SEC. 8 T. 22. R. 12. W.
BOOK PAGE 107 LINE 27

Make