

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
600 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

PAWNEE County. Sec. 16 Twp. 22 Rge. (E) 15(W)

Location as "NE/CNW%SW%" or footage from lines NE SW SE

Lease Owner PETROLEUM, INC.

Lease Name Fertig Well No. 1

Office Address 305 East Third, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 11, 19 53

Application for plugging filed April 11, 19 53

Application for plugging approved April 11, 19 53

Plugging commenced April 11, 19 53

Plugging completed April 11, 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4051 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	251'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 240' and set wooden plug at 240'.

Cemented and displaced 20 sacks cement through drill pipe onto plug at 240'. Mudded up to 35' and set second wooden plug. Filled hole to bottom of well cellar with 10 sacks cement.

4-18-53



Name of Plugging Contractor Garvey Drilling Company
Address 305 East Third, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. W. Fisher (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W. W. Fisher

305 East Third, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April, 19 53

Charlotte Thaidman Notary Public.

My commission expires October 13, 1954



DRILLER'S LOG FERTIG NO. 1

Petroleum, Inc., Operator
 Garvey Drilling Company, Contractor
 Drilling Commenced: March 30, 1953
 Drilling Completed: April 11, 1953
 Casing Record: 8 5/8" @ 251' w/175 sax

Section 16, Twp. 22S., Rge. 15W
 Location: NE SW SE
 County: Pawnee County, Kansas
 R.T.D.: 4051'
 Production: D & A

Figures below indicate bottom of formation:

40 Surface soil
 140 Sand & Shale
 380 Shale & Shells
 420 Red Bed
 515 Sand
 960 Shale & Shells
 998 Anhydrite
 1735 Shale & Shells
 3445 Lime & Shale
 3500 Shale
 3533 Lime & Shale
 3745 Lime
 3903 Lime & Shale
 3935 Chert & Shale
 3979 Cherty Lime
 3993 Shale & Lime
 4001 Shale & Sand
 4051 Lime

Tops:

Heebner: 3420 (-1424)
 Brown Lime: 3533 (-1537)
 Lansing: 3541 (-1545)
 Conglomerate: 3867 (-1871)
 Viola: 3881 (-1885)
 Simpson: 3956 (-1960)
 Arbuckle: 4001 (-2005)

4051' R.T.D.,

I hereby certify that this is a true and correct log of the above mentioned well.

PLUGGING
 FILE SEC. 16 T 22 R 15 W
 BOOK PAGE 92 LINE 29

RECEIVED PETROLEUM, INC.
 STATE CONSERVATION COMMISSION

APR 13 1953

PETROLEUM, INC.

By W. W. Fisher

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 COUNTY OF SEDGWICK)

SS:

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 15th day of April, 1953.

Charlotte Heider
 Notary Public

My commission expires: October 13, 1954.