

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 16 Twp. 22 Rge. 15 (E) (W)

Location as "NE/CNWKSWK" or footage from lines SW SW SW  
Lease Owner Barnett Oil Company  
Lease Name Koehn Well No. 1  
Office Address 411 First National Bank Building Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19\_\_  
Application for plugging filed 19\_\_  
Application for plugging approved 19\_\_  
Plugging commenced 9-30-68 19\_\_  
Plugging completed 10-12-68 19\_\_  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation Depth to top Bottom Total Depth of Well 4003 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	243	None
				4 1/2	None	3587

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in.

Cleaned out cellar. Sanded to 3850'. Dumped 5 sacks of cement.  
Working pipe - 8 5/8 making water.

Broke off casing head. Put on control head, shut off water. Working pipe. Shot pipe at 3570'. Circulating. Spotted 75 bbl of oil with Allied Cement truck.

Working pipe. Pulling pipe.

Pumped 80 bbl of mud and 100 sacks of cement. Cleaning and doping threads and put on pector.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 16 1968

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Forbes Casing Pulling, Inc. CONSERVATION DIVISION  
Address P. O. Box 221 Great Bend, Kansas Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 15 day of October, 19 68

My commission expires May 27, 1968 Notary Public.