

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-20, 546-0001
LEASE NAME Fertig

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1
3300 Ft. from S Section Line
2310 Ft. from E Section Line

LEASE OPERATOR Iannitti Oil Co.

SEC. 16 TWP. 22 RGE. 15 (E) or (W)

ADDRESS Box 308, Great Bend, Kansas 67530

COUNTY Pawnee

PHONE# (316-792-1922) OPERATORS LICENSE NO. 30395

Date Well Completed _____

Character of Well Oil

Plugging Commenced 10-6-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-23-92

The plugging proposal was approved on October 23, 1992 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4250'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	264'	None
				5-1/2"	4248'	1,694.58

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

B.J. pumped 100# hulls, 25 sacks common cement and 5 1/2" plug displaced to 3250' with 1400psi Max-1100 psi-shutin. Shot casing at 3000, 2700', 2400', 2000', 1700'. Pulled 45' of 5-1/2" casing. BJ plugged well with 300# hulls, 10 sacks gel, 50 sacks 60/40 poz-mix cement with 6% gel; 10 sacks gel, 100# hulls, 8-5/8" plug and 120 sacks cement. Max pressure was 400 psi and shutin 200 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Iannitti Oil Co.

STATE OF Kansas COUNTY OF Barton, ss.

OCT 26 1992
CONSERVATION DIVISION
Wichita, Kansas

James W. Rockhold (Employee of Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 23rd day of October, 1992

Jana M. Leatherman
Notary Public

My Commission Expires:

