


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 16 Twp. 22S Rge. (E)15 (W)
Location as "NE/CNW/SW" or footage from lines C.W/2 SW NE
Lease Owner Deck Oil Co.
Lease Name Fertig #1 Well No. _____
Office Address Suite 4000 One Williams Center Tulsa, Okla. 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry & Abandoned
Date well completed 1-24-79 19____
Application for plugging filed 1-24-79 19____
Application for plugging approved 1-24-79 19____
Plugging commenced 1-24-79 19____
Plugging completed 1-24-79 19____
Reason for abandonment of well or producing formation Dry & Abandoned

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st @ 360 w/50 ska
2nd @ 240 w/25 ska
3rd @ 40 ska Rat Hole

2-16-1979
RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1979
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place Wichita, Ks. 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Jack W. Gabbert (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Jack W. Gabbert
830 Sutton Place Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of February, 19 79
Elizabeth J. Edwards
Elizabeth J. Edwards Notary Public.
My commission expires February 6, 1983



GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Fertig #1
 C-4/2-SW-NE Sec 16-22S-15W
 Pawnee County Kansas

Commenced: 1-3-78⁷⁹

Completed: 1-24-78⁷⁹

OPERATOR: Deck Oil Co.

RECEIVED
 STATE CORPORATION COMMISSION

FEB 20 1979

CONSERVATION DIVISION
 Wichita, Kansas

Depth		Formation	Remarks	
From	to			
0	270	Shale-Sand	Run 6 jts of 28# 8 5/8" csg set @ 264' Cemented w/235 sks Common 2% Gel 3% CC PD @ 10:45 p.m. 1-3-78	
270	405	Shale-Redbed		
405	500	Sand		
500	959	Shale-Redbed		
959	981	Anhy		
981	1075	Shale-Shells		
1075	1860	Redbed-Shale-Shells		
1860	1960	Shale-Shells		
1960	3372	Lime-Shale		
3372	3722	Lime		
2480	2908	(Plug Back) Cement		
2908	3570	Lime-Shale		
3570	3996	Lize		
	3996 TD			DRY & ABANDONED

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
 Drillers' Well Log is true and correct to the best of my knowledge and belief and
 according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 30th day of January, 1979.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

