

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-20,578-0000

LEASE NAME Barstow

WELL NUMBER #3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR Woodman-Iannitti Oil

SEC. 14 TWP. 22 RGE. 15 (E) or (W)

ADDRESS Box 308, Great Bend, Ks. 67530

COUNTY Pawnee

PHONE 316-793-1922 OPERATORS LICENSE NO. 6588

Date Well Completed _____

Character of Well Gas

Plugging Commenced 1-18-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-28-91

The plugging proposal was approved on January 17, 1991 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom T.D. 2985'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	225'	None
				5-1/2"	2,983'	1,525.17'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 2850' and 5 sacks cement. Shot casing at 2228', 2137', 2043, 1618; & 1523. Pulled 50 joints of plain and yellowrap 5-1/2" casing. B.J. Services plugged well with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, plug and 125 sacks 60/40 pozmix cement with 6% gel. Max pressure 1100 and shutin 200

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530 STATE OF _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woodman-Iannitti Oil JAN 30 1991

STATE OF Kansas COUNTY OF Barton, ss. _____ 1-30-90

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 29th day of January, 1991

Iona M. Leatherman
Notary Public

My Commission Expires:

