


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 14 Twp. 22S Rge. 15W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C - S/2 S/2 NE

Lease Owner ~~XXXXXXXX~~ F & M Oil Co., Inc.
Lease Name Koehn #1 Well No. _____
Office Address 505 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section List

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9/17/80 _____ 19____
Plugging completed 9/17/80 _____ 19____
Reason for abandonment of well or producing formation
Depleted

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3940
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	247	None
				5-1/2	3936	2924/ft

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Squeezed hole with 3 sacks hulls, 25 sacks gel and 3 sacks hulls.
Released plug and displaced with 150 sacks common cement 4% gel and 3% cc.

Plugging Complete.

9-24-80



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of September, 1980
ELCIE SELLS
Rice County, Ks
My App. Exp. May 31, 1984

[Signature]
Notary Public.

My commission expires MAY 31-1984

DRILLERS' WELL LOG

15-145-20438-0000

DATE COMMENCED: November 1, 1976
DATE COMPLETED: November 12, 1976

F & M Oil Co., Inc.
"KOEHN # 1"
C S/2 S/2 NE
Sec 14-T22S-R15W
Pawnee County, Kansas

ELEVATION: 1970 K.B.

0 - 336'	Surface Soil, Sand, Shale
336 - 913'	Shale, Red Bed
913 - 937'	Anhydrite
937 - 1675'	Shale
1675 - 3379'	Shale and Lime
3379 - 3383'	Shale
3383 - 3415'	Lime and Shale
3415 - 3494'	Shale
3494 - 3503'	Lime and Shale
3503 - 3733'	Lime
3733 - 3763'	Lime and Shale
3763 - 3872'	Lime, Chert, Shale
3872 - 3934'	Chert
3934 - 3940'	Dolomite
3940'	RTD

FORMATION TOPS

Anhydrite	913
Heebner	3379
Douglas	3415
Brown Lime	3494
Kansas City	3503
Base K.C.	3733
Marmaton	3763
Viola	3872
Arbuckle	3934
RTD	3940
PBTD	3940

SURFACE PIPE: Set used 28#,
8 5/8" pipe at 247' w/ 225
sacks Common, 2% Gel, 3% CC.

PRODUCTION PIPE: Set used
5 1/2", 14# casing @ 3936' w/100
sacks Common cement, 2% Gel,
10% salt, 15' bbls salt flush

COPY

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1980
CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 15th day of November, 1976.

Deborah M. Hague
Notary Public

My Commission Expires: April 11, 1978