

15-145-19024-0000

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Graham-Michaelis Corporation

SEC. 14 TWP. 22S RGE. 15W (E) or (W)

ADDRESS P. O. Box 247, Wichita, KS 67201

COUNTY Pawnee

PHONE# (316) 264-8394 OPERATORS LICENSE NO. 5134

Date Well Completed

Character of Well Oil

Plugging Commenced 11-15-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-22-93

The plugging proposal was approved on (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3970'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	250'	none
				5 1/2	3968'	2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 3590' & 5 sks cement. Shot @ 2800', 2600' & 2400'. Came loose, pulled pipe. Pumped 300# hulls, 10 sks gel, 50 sks cement, 10 sks gel, 100# hulls, 8 5/8 plug, 150 sks cement, 60/40 pos, 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graham-Michaelis Corp.

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO

(Employee of Operator) (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 1st day of December, 19 93

Irene Herzberg
 Notary Public

My Commission Expires:



RECEIVED
 STATE CORPORATION COMMISSION
 12-2-93
 CONSERVATION DIVISION
 Wichita, Kansas

Company:	Bennett & Roberts Drig. Inc.	Sec. 14-22-15
Farm:	#1 Hoffman	Loc. Approx. SW SW NW
Total Depth	3970'	County. Pawnee
Comm:	Oct. 3, 1964	
Comp:	Oct. 12, 1964	
Contractor:	Woodman & Iannitti Drilling Co.	
Casing:	8 5/8 @ 250' w/200 sx	
Elevation:	1984 RB	

Figures Indicate Bottom Of Formation

0	90	Sand
90	160	Sand
160	250	Blue Shale
250	300	Shale
300	390	Red Bed
390	470	Sand
470	924	Red Bed
924	951	Anhy.
951	1225	Shale & Shells
1225	1705	Shale & Shells & Red Bed
1705	1895	Shale & Lime
1895	2085	Lime & Shale
2085	2220	Lime & Shale
2220	2255	Lime
2255	2395	Shale & Lime
2395	2610	Shale & Lime
2610	2815	Lime & Shale
2815	2970	Shale & Lime
2970	3125	Shale & Lime
3125	3255	Shale & Lime
3255	3326	Lime
3326	3435	Shale & Lime
3435	3510	Lime & Shale
3510	3545	Lansing Lime
3545	3615	Lime
3615	3640	Lime
3640	3665	Lime
3665	3685	Lime
3685	3755	Lime
3755	3838	Lime
3838	3905	Lime & Chert
3905	3966	Lime
3966	3970	Total Depth

I certify the above to be a true and correct copy of the Driller's log and the Geological tops to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING CO.

H. T. Woodman

K. T. Woodman

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 06 1993

CONSERVATION DIVISION
WICHITA, KS