

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-075-20,301-0000

LEASE NAME Walkinshaw

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
2550' FEL, 1320' FSL
SPOT LOCATION of NE/4

SEC. 32 TWP. 22 RGE. 39 (X) or (W)

COUNTY Hamilton

Date Well Completed 8.10.79

Plugging Commenced 6-3-85

Plugging Completed 6-3-85

LEASE OPERATOR Osborn Heirs Co.
ADDRESS Box 17868, San Antonio, TX 78286

PHONE # (512) 826-0700 OPERATORS LICENSE NO. 5249

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Winfield Depth to top 2713 bottom 2723 T.D. 2736'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	335'	0'
Production				5 1/2"	2736'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls & 25 sks. cement to 2350' Displaced w/mud to 1780' & pumped 50 sks. cement 1780' to 1100' Displaced w/mud to 360' and pumped 50 sks. cement 360' to 0' Pressured to 600 lbs., cut off 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
Address Box F, Sublette, Ks. 67877

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Haskell, ss.

I, Edgar J. Eves

(operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves
(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 5th day of June, 1985

Sandra L. Eves
Notary Public

My Commission expires: 12-6-88

