

TIGHT

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
600 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-075-20565-0000

LEASE NAME Susanna Salter

WELL NUMBER 1-26

3630 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 26 TWP. 22S RGE 39 (E) or (W)

COUNTY Hamilton

Date Well Completed 8-14-95

Plugging Commenced 8-14-95

Plugging Completed 8-14-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Amoco Production Company

ADDRESS PO Box 800 Room 924 Denver, CO 80201

PHONE (303) 830-5323 OPERATORS LICENSE NO. 5952

Character of Well Dry

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 11, 1995 (date)

BY Steve Middleton (KCC District Agent's Name).

ACO-1 filed? No If not, is well log attached? ACO-1 and logs are being sent in at the same time as this report.

Producing Formation Dry Depth to Top Bottom Bottom T.O.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8.625"		499'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

The well was plugged using 60/40 PDZ w/ 6% Gel. as follows: Plug No 1-2330' w/ 50 sx cement; Plug No 2-960' w/ 80 sx cement; Plug No 3-520' w/ 50 sx cement; Plug No 4-40' w/ 10 sx cement; Rathole w/ 15 sx cement; Mousehole w/ 10 sx cement. Cut off casing and capped well.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. RECEIVED  
KANSAS CORPORATION COMMISSION

Address \_\_\_\_\_

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Amoco Production Company SEP 18 1995

STATE OF Colorado COUNTY OF Denver 9-18-95  
CONSERVATION DIVISION  
WICHITA, KS

Samuel J. Carmack (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Samuel J. Carmack

(Address) 2225 West Oklahoma Ulysses, KS

SUBSCRIBED AND SWORN TO before me this 13th day of September, 19 95

Donna J. Monroe  
Notary Public

My Commission Expires May 4, 1999