


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Long Building
Wichita, Kansas

Finney County. Sec. 7 Twp. 22 Rge. 33 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Trans Era Petroleum Inc.
Lease Name Rodgers # 1 Well No. _____
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5/2/53 19_____
Application for plugging filed April 30, 1953 19_____
Application for plugging approved April 30, 1953 19_____
Plugging commenced May 1, 1953 19_____
Plugging completed May 1, 1953 19_____
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19_____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4860 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	219'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Lay down one-half of drill pipe. Pumped hole full of heavy mud layed down balance of drill pipe. Filled hole to 215 feet, set first plug with twenty sacks cement. Filled hole with heavy mud to 40 feet, set second plug with one-half sack hulls and ten sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
W. A. Michaelis Jr. (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. A. Michaelis Jr.
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 1953

My commission expires January 30, 1957

Margie Cooper Notary Public.

24-7368-5 3-53-20M

RECEIVED
STATE CORPORATION COMMISSION

JUN 25 1953 6-5-53

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 7 T 22 R 33W
BOOK PAGE 48 LINE 41

Trans Era Petroleum, Inc.
Rodgers # 1

SE SE SE 7-22-33
Finney County, Ks.

Total Depth: 4860'
Comm: 4/5/53
Comp. 5/2/53

Casing 8 5/8" set @ 219'
Cement 200 sacks bulk

Formation	Depth
Shale - sand	60
Sand	90
Gravel - shells	165
Shale - sand - shells	200
Shale	2210
Blue shale	220
Shale	825
Shale - sand	940
Sand	1015
Red bed	1170
Red bed - shale	1350
Anhydrite - shale	1500
Shale	1570
Shale - salt	1710
Shale - red bed	2306
Lime - shale	3030
Lime	3085
Lime - shale	3185
Lime	3214
Lime - shale	3915
Lime	4668 1/2
Shale - lime	4710
Lime	4860

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Lois Hanson

Subscribed and sworn to before me this 3rd day of June, 1953.

Margie Cooper
Notary Public, Russell County, Ks.

My Commission Expires:
January 30, 1957

PLUGGING
FILE REC-7-T-22-R-39a
BOOK PAGE 98 LINE 41

CONSERVATION DIVISION
Wichita, Kansas