

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER Completed 06-09-63

LEASE NAME Billings "B"

WELL NUMBER No. 1

 Ft. from S Section Line

 Ft. from E Section Line

C NE NE
SEC. 35 TWP. 22S RGE. 23W XXX or (W)

COUNTY Hodgeman

Date Well Completed 06-09-63

Plugging Commenced 09-21-87

Plugging Completed 09-25-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Rt. #3, Box 20-A, Great Bend, Kansas 67530

PHONE# (316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1, Dodge City, Kansas

Is ACC-1 filed? Yes If not, is well log attached?

Producing Formation Mississippi Depth to Top 4493 Bottom 4500 T.D. 4500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pulled rods & pmp. Left pkr @4350'. COOH w/tbg. MIRU Great Guns to set CIBP @ 4355'. Dmpd 2' sx cmt w/boiler on top of plug. Perf csg @ 850' w/squeeze gun 2"-2 SPF. MIRU BJ-Titan. Hook up to 5 1/2" csg. Pmpd 125 sx Econolite cmt. 0 press. Pmpd 100 sx dn anls, 200# SIP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Titan, Inc. License No.

Address 925 Patton Road, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

S. J. Reynolds (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *S. J. Reynolds*

(Address) Rt. #3, Box 20-A, Great Bend, KS

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 19 87

Patricia L. Prosser
Notary Public

My Commission Expires: 07-30-90

NOV 4 1987



11-4-87

CONSERVATION DIVISION
Wichita, Kansas