



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 3 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Blevins of Leben Drilling Inc. & Jones-Gebert Drilling Co. has this

date requested permission to plug the following described well:

Mr. Blevins guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling Inc. & Jones-Gebert Drilling Co.

Complete Address: 905 Central Bldg. Wichita, Kansas

Lease Name: Johnson Well No. 1

Location: C NE NW Sec. 10 Twp. 23 Rge. 25 (E) (W)

County Hodgeman Total Depth 4765' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Blevins was instructed to plug the well as follows:

8 5/8"-235' Circulated w/cement.

Mud 4765' to 700' Spotted 25 Sax.cement 700' to 625'

Mud 625' to 225' Spotted 25 Sax.cement 225' to 150'

Mud 150' to 40' Plug,Hulls,15 Sax.cement 40' to 0

Very truly yours,

F. Hugh Scott
Conservation Division Agent