

State of Kansas



FORM CP-2

15.083.20871.00.00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

July 30, 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Bill Roach of Husky Drilling Co, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: American Energies Corporation

Complete Address: 575 Fourth Financial Center, Wichita, Kansas 67202

Lease Name: Koontz Well No. 1

Location: C SW NE Sec. 26 Twp. 23 Rge. 22 (E) (W)

County: Hodgeman Total Depth: 4535'

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereafter indicated:

Mr. Roach was instructed to plug the well as follows:

8 3/8" - 307' - 260' sacks 60-40 2 1/2 gal 3 1/2 cc. Circulate hole and Fill with mud. Pump 50 sacks cement through drill pipe at 1100'. Pump 50 sacks cement through drill pipe at 400'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rat hole with 10 sacks cement. Elev. 2212 GL Anhydrite 1512'-1548' Top Dakota 700'.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

William J. Larson
Conservation Division Agent

AUG 6 1981
CONSERVATION DIVISION
Wichita, Kansas

8-6-81