

State of Kansas



15.083.10200.00.00

FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

DEC 16 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Marvin Blankenship of Phillips Petroleum Co. has this
 date requested permission to plug the following described well:

Mr. Blankenship guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Co.

Complete Address: Box 287, Great Bend, Kansas

Lease Name: Querbach Well No. # 1

Location: C SE SW Sec. 22 Twp. 23 Rge. 22 (E) (W) W

County Hodgeman Total Depth 4700 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Blankenship was instructed to plug the well as follows:

243' of 8 5/8" surface pipe, cement circulated. Fill hole
with drilling mud. Spot 25 sacks cement, through drill
pipe, at 700'. Pull up to 240', and spot 25 sacks cement
through drill pipe. Fill hole with drilling mud to 40',
Plug bridged with hulls, cemented with 15 sacks to base
cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent