



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 12 1963  
11 -12-63

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Jones of Murfin Drilling Company has this  
 date requested permission to plug the following described well:

Mr. Jones guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company

Complete Address: 617 Union Center. Wichita, Kansas

Lease Name: Querback Well No. 1

Location: C SW NE Sec. 10 Twp. 23S Rge. 22 (E) (W)

County Hodgeman Total Depth 4505' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Jones was instructed to plug the well as follows:

8 5/8"-276' Circulated w/cement.

Mud 4505' to 500' Spotted 25 Sax.cement 500' to 425'

Mud 425' to 270' Spotted 25 Sax.cement 270' to 195'

Mud 195' to 40' Plug,Hulls,10 Sax.cement 40' to 0

Very truly yours,

*J. P. Roberts*  
 Conservation Division Agent