

State of Kansas



15.083.30096.00.00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1966
9-23-66

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Mallonee of Mallonee-Coppinger Oper. has this
date requested permission to plug the following described well:

Mr. Mallonee guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Coppinger Operations, Inc.

Complete Address: L207 Union National Building, Wichita, Kansas

Lease Name: Mooney Well No. 1

Location: C SW SE Sec. 33 Twp. 23 Rge. 21 (E) (W)

County Hodgeman Total Depth 4756' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mallonee was instructed to plug the well as follows:

- 8 5/8" to 271' circulated w/ cement. T.D. 4756'
- Mud 4756' To 630' Spotted 30 sacks cement 630' to 530'
- Mud 530' to 320' Spotted 35 sacks cement 320' to 220'
- Mud 220' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Frank Ewen
Conservation (Division Agent)