



15.083.300/0.00.00

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1965
4-20-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Raymond of Raymond Oil Co., Inc. has this

date requested permission to plug the following described well:

Mr. Raymond guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Co., Inc.

Complete Address: 410 Fourth Natl. Bk. Bldg. Wichita, Kansas

Lease Name Kingry Well No. # 1

Location: C NW NE Sec. 10 Twp. 23S Rge. 21 (E) (W)

County Hodgeman Total Depth 4678' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Raymond was instructed to plug the well as follows:

9" 335' Circulated w/cement.

Mud 4678' to 700' Spotted 25 Sax. cement 700' to 625'

Mud 625' to 350' Spotted 25 Sax. cement 350' to 275'

Mud 275' to 45' Plug, Hulls, 15 Sax. cement 45' to 0

Very truly yours,

Conservation Division Agent