



15-083-20044-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Buchheister of John O. Farmer has this

date requested permission to plug the following described well:

Mr. Buchheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer Inc.

Complete Address: 370 W. Wichita Ave., Russell, Kansas

Lease Name: Stapleton "B" Well No. 1

Location: C SW NE Sec. 14 Twp. 22 Rge. 26 (E) (W)

County Hodgeman Total Depth 4602' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buchheister was instructed to plug the well as follows:

- 8 5/8" to 210' circulated w/ cement. Mud 4602' to 900'
- Spotted 80 sacks cement 900' to 650' Mud 650' to 300'
- Spotted 50 sacks cement 300' to 150' Mud 150' to 45'
- Plug, Halls & 15 sacks cement 45' to 0'

Very truly yours,

Edgar J. Eves
Conservation Division Agent