



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

MAR 28 1972

CONSERVATION DIVISION
Wichita, Kansas

3-28-72

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hanna of Anadarko Production has this
date requested permission to plug the following described well:

Mr. Hanna guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Adams "C" Well No. 2

Location: C SW NE Sec. 25 Twp. 34 Rge. 31 (E) (W)

County: Seward Total Depth 4390' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hanna was instructed to plug the well as follows:

8 5/8" to 1274' circulated w/ cement. 4 1/2" to 4389' cemented.

Top perforations 4149' Plug bottom w/ 20 sacks cement.

Top of cement 3850' Mud 3850' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent