

15-175-20149-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hughes of Hughes has this

date requested permission to plug the following described well:

Mr. Hughes guarantees payment of the plugging fee.

Operator's full Name: William G. Hughes

Complete Address: 5610 S. 77th Ave, Tulsa, Oklahoma

Lease Name: Adams 25-A Well No. 1

Location: C NE SW Sec. 25 Twp. 34 Rge. 31 XX (E) (W)

County: Seward Total Depth 4461' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hughes was instructed to plug the well as follows:

8 5/8" to 1388' circulated w/ cement. 4 1/2" to 4461' cemented.


Top perforations 4372' Plug bottom w/ 20 sacks cement.

Top of cement 4200' Mud 4200' to 800'

Spot 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent