

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1974
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hughes of Hughes has this

date requested permission to plug the following described well:

Mr. Hughes guarantees payment of the plugging fee.Operator's full Name: William G. HughesComplete Address: 5610 S 77th E Ave, Tulsa, OklahomaLease Name: Adams 25-B Well No. 1Location: SE NW Sec. 25 Twp. 34 Rge. 31 ^{XY}(E)(W)County: Seward Total Depth 4400 Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Hughes was instructed to plug the well as follows:8 5/8" to 1281' circulated w/ cement. 4 1/2" to 4400' cemented.Top perforations 4287' Plug bottom w/ 20 sacks cement.Top of cement 4000' Mud 4000' to 800'Spot 35 sacks cement 800' to 700' Mud 700' to 45'Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent