

EP

State of Kansas



15-175-20008-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

AUG 23 1967  
8-23-67

CONSERVATION DIVISION  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Lowery of Petroleum Inc. has this

date requested permission to plug the following described well:

Mr. Lowery guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: Box 1255, Liberal, Kansas

Lease Name: Adams "0" Well No. 1

Location: App C SW SE Sec. 25 Twp. 34 Rge. 31  (W)

County Seward Total Depth 6165' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Lowery was instructed to plug the well as follows:

8 5/8" to 1305' circulated w/ cement. 4 1/2" to 6150' cemented.

Top perforations 5998' Plug bottom w/ 15 sacks cement

Top of cement 5800' Mud 5800' to 700'

Spotted 40 sacks cement 700' to 600' Mud 600' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'

Very truly yours,

E. Edward Johnson  
Conservation Division Agent