

15-083-10147-0000

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1966

9-8-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Pulley of Kewanee Oil Co. has this

date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Kewanee Oil Company

Complete Address: Box 360, Hoisington, Kansas

Lease Name: Staley "W.I." Well No. 4

Location: SE NW NW Sec. 15 Twp. 22 Rge. 25 (E) (W)

County Hodgeman Total Depth 4700' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pulley was instructed to plug the well as follows:

8 5/8" to 562' circulated w/ cement. Top perforations 4612'

Plug, bottom w/ sand & 5 sacks cement, Top of cement 4550'

Mud 4550' to 550' Spotted 25 sacks cement 550' to 475'

Mud 475' to 45' Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Edward J. Eves
Conservation Division Agent