

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 28 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Anadarko Production Co.

Complete Address Box 351, Liberal, Kansas

Lease Name Adams "C" Well No. 2

Location C SW NE Sec. 25 Twp. 34 Rge. 31 (E) (W)

County Seward Total Depth 4390'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 22 Month 3 Year 1972

The above well was plugged as follows:

8 5/8" to 1274' circulated w/ cement. 4 1/2" to 4389' cemented.

Top perforations 4149' Plug bottom w/ 20 sacks cement.

Top of cement. 3850' Mud 3850' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Company Pump

Pulled 3225' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edward J. Eads*  
Well Plugging Supervisor

INVOICED

DATE 3-30-72

INV. NO. 5432-10