

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name William G. Hughes

Complete Address 5610 S. 77th E Avenue, Tulsa, Oklahoma 74145

Lease Name Adams 25-A Well No. 1

Location C NE SW Sec. 25 Twp. 34 Rge. 31 (E) (W)

County Seward Total Depth 4461'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargent Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 5:00PM Day 29 Month 1 Year 1974

The above well was plugged as follows:

8 5/8" to 1388' circulated w/ cement. 4 1/2" to 4461' cemented.

Top perforations 4372' Plug bottom w/ 20 sacks cement.

Top of cement 4200' Mud 4200' to 800'

Spotted 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2604' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/8/74
" 8536-WSigned: Edgar J. Curd
Well Plugging Supervisor