

KANSAS

*W*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AGT 24 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Mc Adams Pipe & Supply, Inc.

Complete Address: Drawer 960, Bristow, Oklahoma 74010

Lease Name Brown Well No. 2

Location SE SW NW Sec. 8 Twp. 22 Rge. 9 (E) (W) X

County Reno Total Depth 3638'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 10 AM Day 17 Month October Year 1967

The Above well was plugged as follows:

Hole filled with sand to 3630' and cemented with 5 sacks.

Rock bridge set from 235' to 225' and 10 sacks cement dumped on bridge and left to

set over-night. Hole bailed dry to top of cement (200') and hole cemented with 15

sacks (total 25 sacks). Hole filled with mud to 40'. Rock bridge set from 40' to

30' and hole cemented to base of cellar with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. J. [Signature]*  
Well Plugging Supervisor

DATE 10/24/67  
INV. NO. 6555-W