

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1967
10-24-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mc Adams Pipe & Supply, Inc.

Complete Address: Drawer 960, Bristow, Oklahoma 74010

Lease Name Brown Well No. 1

Location SE SE NW Sec. 8 Twp. 22 Rge. 9 (E) (W) X

County Reno Total Depth 3652'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 11:30 AM Day 17 Month October Year 1967

The Above well was plugged as follows:

Hole filled with sand to 3600' and cemented with 3 sacks.

Rock bridge set from 200' to 190'. 10 sacks cement dumped on bridge and left to set

over-night. Hole bailed dry to top of cement (160') and cemented with 15 sacks (total

25 sacks). Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole

cemented to base of cellar with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. J. ...*
Well Plugging Supervisor

DATE 10/24/67

INV. NO. 6554-W