

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15- 083-20,888:00.00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Energy Methods Corporation

Complete Address 1616 Glenham Pl # 2850, Denver Colo

Lease Name EMC - Wade Well No. 1-36

Location 1980 FSL-1980 FEL ^{CNWSE} Sec 36 Twp. 23 Rge. 23 (East) (West)

County Hodgeman Total Depth 4720

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor White + Ellis Drilling

Address El Dorado, Kansas License No. _____

Operation Completed: Hour: 9:30 PM Day: 3 Month: Sept Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

There was 566' of 8 1/8" surface casing. Cement
circulated with 300 lbs cement with 2% Z⁷⁰
Gell + 3% C.C. Filled with heavy mud to
1075'. 1st plug at 1050-900'. 1st plug at
1075' with 75 lbs cement. Filled with
heavy mud to 540'. Pashed rubber plug to
540'. 2nd plug at 540' with 40 lbs cement.
Filled with mud to 40'. built solid bridge
at 40'. 3rd plug at 40-0 with 10 lbs cement.

I hereby certify that the above well was plugged as herein stated.

5 Sheen at hole.

Signed: [Signature]
Conservation Division Agent
STATE CORPORATION COMMISSION
RECEIVED
SEP - 8 1981
CONSERVATION DIVISION
Wichita, Kansas

DATE 10-28-81

INV. NO. 8087-W