

15.083.10343.00.00

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

AUG 17 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name E. F. Lippoldt "D" Well No. # 1

Location C NW NW Sec. 23 Twp. 23 Rge. 23 (E)    (W) W

County Hodgeman Total Depth 4625

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X

Other well as hereafter indicated:   

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 12:00PM Day 15th Month August Year 1964

The Above well was plugged as follows:

253' of 8 5/8" surface pipe, cement circulated. 4584' of 4 1/2" long string,  
cemented with 100 sacks. Bottom of hole was sanded to 4575', and cemented  
with 20 sacks. Pipe was pulled up to 720', and 10 sacks of Gel-Mud was pumped,  
through 4 1/2" swage. Pipe was pulled up to 660', and 25 sacks cement  
pumped. Pipe was pulled up to 270', and 5 sacks of Gel-Mud pumped. Pipe was  
pulled up to 240', and 25 sacks of cement was pumped, through swage, into  
4 1/2" casing. Hole was bailed down to 40', bridge plug set on fluid at 40',  
and 10' of rock bridge, cemented with 10 sacks to the base of the cellar.  
3608' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-18-64

INV. NO. 9651-W

Signed: Archie Elving  
Well Plugging Supervisor