

15.083.10200.00-00

Form CP-3
Rev. 6-26-62

W
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1963

CONSERVATION DIVISION
Wichita, Kansas

12-16-1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Phillips Petroleum Co.

Complete Address: Box 287, Great Bend, Kansas

Lease Name Querbach Well No. # 1

Location C SE SW Sec. 22 Twp. 23 Rge. 22 (E) (W)

County Hodgeman Total Depth 4700

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Co.

Address: Route 2, Great Bend, Kansas License No.

Operation Completed: Hour 6:45PM Day 14th Month December Year 1963

The Above well was plugged as follows:

243' of 8 5/8" surface pipe, cement circulated. Hole was filled with
drilling mud. At 700', 25 sacks cement was pumped into drill pipe. At
240', 25 sacks cement was pumped into drill pipe. Hole was filled with
drilling mud to 40', cementing plug, bridged with hulls, cemented
with 15 sacks to base cellar. Rat hole bridged and cemented with 3 sacks.
The cementing of the plugs was done by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/19/63

INV. NO. 8295-u