


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 20 Twp. 22S Rge. (E) 12 (W)
Location as "NE/CNW/SE" or footage from lines NE NE SE
Lease Owner Beardmore Drilling Company
Lease Name Anderson Well No. 1
Office Address 603 Petroleum Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 12-31 19 52
Application for plugging filed 12-31 19 52
Application for plugging approved 12-31 19 52
Plugging commenced 12-31 19 52
Plugging completed 12-31 19 52
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3761 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Sand & Shale		0	224	8-5/8"	224	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

Heavy Mud from 3761 to 210'
Wood Plug at 210'
20 Sacks Cement 210' to 150'
Heavy Mud from 150' to 35'
Wood Plug at 35'
10 Sacks Cement 35' to ground

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Company
Address 603 Petroleum Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, Heber Beardmore, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore
603 Petroleum Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of January, 1953

My commission expires January 28, 1956

24-2675-5

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1953
CONSERVATION DIVISION
Wichita, Kansas
1-10-53

PLUGGING
WELL SEC 20 T 22 S R 12 W
BOOK PAGE 20 LINE 6

ANDERSON NO. 1

NE NE SE
Section 20-22S-12W,
Stafford County, Kansas

Drilled for: Beardmore Drlg. et al
Drilled by: Beardmore Drlg. Co.

Casing Record:

8-5/8" 224' w/150 Sacks

Drilling Commenced: December 18, 1952
Drilling Completed: December 31, 1952

Elevation: 1874 DF
1871 GR

<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5
Clay Sand	40
Sand	210
Red Rock - Shale	224
Red Bed	665
Anhydrite	690
Shale - Shells	1390
Shale - Lime	1645
Lime - Shale	2855
Lime	3100
Lime - Shale	3175
Lime	3761 T. D.

D & A.

TOPS:

Heebner	3184
Lansing	3334
Arbuckle	3728

DST #1 - 3355--3422 - Open 1 hour, weak blow, recovered 30' mud, few spots of oil, BHP 110#

DST# 2 - 3503 - 3538- Open 1 hour, fair blow throughout test, recovered 30' mud with few specksof oil. BHP Zero.

STATE OF KANSAS

COUNTY OF SEDGWICK

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above-described, to the best of my knowledge and belief.



Subscribed and sworn to before me this 8th day of January, 1953.

Leonard P. Tolle
Notary Public

My commission expires January 28, 1956.

