


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Reno County, Sec 8 Twp. 22 Rge. 9 (E) (W)
Location as "NE/CNW%SW%" or footage from lines SW SE SW
Lease Owner Sterling Drilling Company
Lease Name Kilbourne #3 Well No.
Office Address Sterling, Kansas 67579
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12/23/68 19
Plugging completed 12/27/68 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation Depth to top Bottom Total Depth of Well 3670 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	234'	none
				5 1/2"	3670'	3183'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3640', ran sand to 3600', mixed and dumped 5 sacks of cement. Loaded hole, shot pipe at 3174', pipe came loose, pulled 101 joints. Bailed fluid down to 230', set 10' rock bridge and dumped 25 sacks of cement. Mudded to 40', 10' rock bridge and ran 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 68

My commission expires February 15, 1971

Margaret McLehee
Notary Public.

STERLING DRILLING COMPANY
Sterling, Kansas 67579

WELL LOG ----- KILBOURN #3
LOCATED: SW SE SW, Section 8-22S-9W, Reno County, Kansas

OWNER: STERLING DRILLING COMPANY, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

TOTAL DEPTH: 3670'

RECEIVED
STATE CORPORATION COMMISSION
DEC 5 1968
CONSERVATION DIVISION
Wichita, Kansas

LOG

CASING RECORD

0 - 100	Clay and sand
100 - 235	Sand and Red Bed
235 - 525	Red Bed and Shale
525 - 1060	Shale
1060 - 1360	Shale and Lime
1360 - 1560	Shale and Lime
1560 - 1750	Shale and Lime
1750 - 1825	Lime
1825 - 1925	Lime and Shale
1925 - 2170	Shale
2170 - 2375	Shale
2375 - 2520	Shale and Lime
2520 - 2655	Lime and Shale
2655 - 2760	Lime
2760 - 2850	Lime
2850 - 2900	Lime and Shale
2900 - 3050	Shale and Sand
3050 - 3056	Shale
3056 - 3140	Lime
3140 - 3215	Lime
3215 - 3260	Lime
3260 - 3345	Lime
3345 - 3415	Lime
3415 - 3470	Shale and Conglomerate
3470 - 3481	Sand
3481 - 3535	Shale
3535 - 3595	Lime
3595 - 3608	Lime
3608 - 3617	Shale and Sand
3617 - 3622	Sand
3622 - 3630	Simpson
3630 - 3670	Sand and Shale

Set 234' 8 5/8" surface casing, 200 sks,
2% c.c.

Set 3689.93' of 5 1/2" casing, set at 3670'
with 75 sacks cement.