

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Reno County. Sec. 17 Twp. 22S Rge. (E) 9 (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW

Lease Owner Thunderbird Drilling, Inc.

Lease Name Drake Well No. #1 "X"

Office Address 712 Union Center

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed XXXX March 30 19 59

Application for plugging filed April 17 19 59

Application for plugging approved Oral permission granted 19

Plugging commenced March 30 19 59

Plugging completed March 30 19 59

Reason for abandonment of well or producing formation Lost Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred W. Hampel, Pretty Prairie, Kansas

Producing formation Depth to top Bottom Total Depth of Well 2425 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	221'	8 5/8"	224.79	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 180'. Set plug at 180' with 1/2 sack hulls, and 15 sacks of cement. Filled hole with mud to 40'. Set plug at 40' with 1/2 sack of hulls and 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1959

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Thunderbird Drilling, Inc.
Address 712 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Charles W. Aikins, Jr.

(If additional description is necessary, use BACK of this sheet)
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

712 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of April, 19 59

My commission expires Sept. 5, 1960

Jenell Schartz
Notary Public.

PLUGGING

FILE SEC. 17 T. 22 R. 9 W
BOOK PAGE 30 LINE 44

THUNDERBIRD DRILLING, INC.

#1 "X" DRAKE - WELL LOG

LOCATION:

NW NW SW Sec. 17-Twp. 22.S-
Rge. 9.W, Reno County, Kansas

CONTRACTOR:

Thunderbird Drilling, Inc.
712 Union Center
Wichita, Kansas

SURFACE CASING:

8 5/8" set at 221 with 175 sacks of
cement, 2% gel, 3 sacks of Calcium
Chloride.

OIL STRING:

None

ELEVATION:

1733' K.B.
1730' D.F.
1728' G.L.

COMMENCED:

March 25, 1959

COMPLETED:

March 30, 1959

WELL LOG

0 - 153	Sand
153 - 221	Shale
221 - 350	Shale & Shells
350 - 390	Anhydrite
390 - 640	Shale
640 - 1180	Shale & Shells
1180 - 1375	Shale & Lime
1375 - 1845	Lime
1845 - 2425	Lime & Shale
2425	Rotary Total Depth

The undersigned, Charles W. Aikins, Jr., an officer of Thunderbird Drilling, Inc., hereby certifies that the above is a true and correct log of the formations encountered in the drilling of the #1/ Drake as shown in the daily drilling reports.


"X"

Thunderbird Drilling, Inc.

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1959


CONSERVATION
CONSERVATION DIVISION
Wichita, Kansas



Charles W. Aikins, Jr., Pres.

Subscribed and sworn to before me this

17th day of April, 1959.


Jewell Schartz - Notary Public

My commission expires:

September 5, 1960.

PLUGGING

FILE SEC. 17 T. 22 R. 9W
BOOK PAGE 30 LINE 44