

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-055-20393-0000

LEASE NAME Powell

WELL NUMBER 1-33

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 33 TWP. 22 RGE. 27 (E) or (W)

COUNTY Finney

Date Well Completed 1-18-80

Plugging Commenced 12-8-87

Plugging Completed 12-8-87

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS Post Office Box 558, Garden City, Ks.

PHONE # (316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? Previously filed

Producing Formation Cherokee Cong Depth to Top 4574 Bottom 4588 T.D. 4865

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cherokee Conglomerate	oil	4574	88	5 1/2 14#	4767	0
						TOC @ 3350', F.S.
						CLBP @ 4590'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Rig up Howco to 5 1/2" csg and plug as follows: 25 sks 60/40 poz, 6% gel from 4300 to 4590', 61 bbl 9# mud from 1800' to 4300', 25 sks 60/40 poz 6% gel from 1500' to 1800', 8 bbl 9# mud from 1200' to 1500' and 110 sks 60/40 poz 6% gel from 1200' back to surface. Squeezed well to 1500#. Used 2 sks hulls in first 20 bbl mud

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton

Address Ness City, Kansas

RECEIVED
 STATE CORPORATION COMMISSION
 License No.

12-9-97 REC 9 1987

STATE OF Kansas COUNTY OF Finney

CONSERVATION DIVISION
 Wichita, Kansas

Millard Lindsay

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Millard Lindsay

(Address) P.O. Box 558, Garden City, Ks.

SUBSCRIBED AND SWORN TO before me this 8th day of December, 19 87

Betty J. Purcell
 Notary Public

My Commission Expires: Aug. 6, 1990