

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

FINNEY County. Sec. 14 Twp. 22S Rge. (E) 29 (W)

Location as "NE/CNW%SW%" or footage from lines. C. NE/4 SW/4

Lease Owner. MACK OIL CO.

Lease Name. MAI Well No. 1

Office Address. BOX 400 DUNCAN, OKLAHOMA 73533

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 12-31-76 19

Application for plugging filed YES NOVEMBER 22 1977

Application for plugging approved 19

Plugging commenced NOVEMBER 21 1977

Plugging completed NOVEMBER 21 1977

Reason for abandonment of well or producing formation No commercial quantity of oil or gas found.

If a producing well is abandoned, date of last production -- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. FRANK BROADFOOT

Producing formation Depth to top Bottom Total Depth of Well 4820 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	370'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran 2-3/8" tubing to 400'. Pumped 50 sacks cement from 400' into surface casing at 250'. Pull 10 jts of tubing & pump 15 sacks cement from 60' to surface of ground. Placed 5 sacks cement in rat hole. Pulled remainder of tubing from hole.

RECEIVED
STATE CORPORATION COMMISSION

NOV 28 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor MACK OIL CO.

Address P. O. BOX 400 DUNCAN, OKLAHOMA 73533

STATE OF OKLAHOMA, COUNTY OF STEPHENS, ss.

CARL A. BENTLEY (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl A. Bentley

P. O. BOX 400 DUNCAN, OKLAHOMA 73533 (Address)

SUBSCRIBED AND SWORN TO before me this 22 day of NOVEMBER, 19 77

My commission expires 3-24-79

Josephine Bentley Notary Public.

DST #4

St. Louis-Spergan

4660-4735', 30-60-60-90
 Strong blow through-out opens,
 NGTS.
 IHP 2266
 IFP 91-527
 ICIP 1316
 FFP 549-909
 FCIP 1090
 FHP 2221
 BHT 110 degrees
 Rec. 2400° MSW

FORMATION TOPS

FORMATION	SAMPLE TOP	DATUM	E-LOGS
Hollenberg	2527	+148	2527
Herrington	2543	+132	2543
Krider	2570	+105	2570
Winfield	2621	+ 54	2623
Ft. Riley	2699	- 24	2697
Florence	2750	- 75	2750
Wreford	2879	-204	2880
Council Grove	2911	-236	2913
Cottenwood	3037	-362	3035
Neva	3075	-400	3068
Red Eagle	3124	-449	3119
Admire	3252	-572	3249
Wabaunsee	3410	735	3392
Tarkio	3518	-843	3513
Howard	3610	-935	3609

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 28 1977
 CONSERVATION DIVISION
 Wichita, Kansas

5

FORMATION	SAMPLES TOP	DATUM	E-LOG
Topeka	3660	- 985	3658
Heebner	3870	-1195	3870
Toronto	3888	-1213	3888
Douglas	3901	-1226	3908
Lansing	3916	-1241	3914
Lane Sh.	4096	-1419	4104
Iola	4108	-1433	4113
Chanute	4133	-1458	4133
Drum	4157	-1462	4137
Hackberry Cv.	4167	-1492	4170
Cherryvale	4209	-1534	4205
Dennis (L. Hackberry)	4214	-1539	4222
Stark	4250	-1575	4249
Swope	4255	-1580	4251
B/KC	4335	-1660	4342
Ft. Scott	4456	-1781	4458
Cherokee	4473	-1798	4423
Penn. Basal Sd.	4580	-1905	4570
St. Gen.	4586	-1911	4590
St. Louis	4608	-1933	4606
Spergan	4716	-2041	4722
Osage	4789	-2114	4781
RTD	4820		
LTD			4827

RECEIVED
STATE CORPORATION COMMISSION

NOV 28 1977

CONSERVATION DIVISION
Wichita, Kansas