

State of Kansas



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg.  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 30 1968  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

December 23, 1968

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: P.O. Box 129, Sterling, Kansas 67579

Lease Name: Kilbourn Well No. 3

Location: SW SE SW Sec. 8 Twp. 22 Rge. 9  (E)  (W)  X

County: Reno Total Depth 3670' Oil Well  X

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3600' and cement with 5 sacks cement.

Fill hole with mud to 230'. Set rock bridge from 230' to 220' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set

rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
Conservation Division Agent