

State of Kansas



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GIAVES Gen. Counsel

## State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1968  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

12-23-68

December 16, 1968

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: P.O. Box 129, Sterling, Kansas 67579

Lease Name: Kilbourn Well No. 2

Location: NE SW SW Sec. 8 Twp. 22 Rge. 9 (E) (W) X

County: Reno Total Depth 3670' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3600' and cement with 5 sacks cement.

Fill hole with mud to 220'. Set rock bridge from 220' to 210' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set

rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
Conservation Division Agent