

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

October 10, 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

OCT 14 1963

Dear Sir:

CONSERVATION DIVISION
 Wichita, Kansas

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling has this

date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Lario Oil & Gas Company

Complete Address: 301 So. Market, Wichita 2, Kansas

Lease Name: Schmucker Well No. 1

Location: NW NW SE Sec. 8 Twp. 22 Rge. 9 (E) (W) X

County Reno Total Depth 3656' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Glenn was instructed to plug the well as follows:

Push 4½" plug to 3600'. Fill hole with sand to 3590' and

cement with 3 sacks. Fill hole with mud to 220'. Set

rock bridge from 220' to 210' and cement with 20 sacks.

Fill hole with mud to 40'. Set rock bridge from 40' to

30' and cap hole with 10 sacks cement.

Very truly yours,

Arthur J. Lomax
 Conservation Division Agent