

State of Kansas



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

March 6, 1969

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 25 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. R. E. Smith of Glenn & Smith Pipe Pulling Co has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Lario Oil & Gas Company

Complete Address: 301 S. Market, Wichita, Kansas 67202

Lease Name: Ed. Drake "A" Well No. 3

Location: NW NE NW Sec. 17 Twp. 22 Rge. 9 (E) (W) X

County: Reno Total Depth 3672' Oil Well     

Gas Well      Input Well X SWD Well      D & A      Lost Hole     

Mr. Smith was instructed to plug the well as follows:

Fill hole with sand to 3625' and cement with 5 sacks cement.

Fill hole with mud to 220'. Set rock bridge from 220' to 210' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
Conservation Division Agent