



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

March 21, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 APR 1 1969
 CONSERVATION DIVISION
 Wichita, Kansas

4-1-69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. R. E. Smith of Glenn & Smith Pipe Pulling Co has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Lario Oil & Gas Company

Complete Address: 301 S. Market, Wichita, Kansas 67202

Lease Name: E. Drake "A" Well No. 1

Location: NW NW NW Sec. 17 Twp. 22 Rge. 9 (E) (W) X

County: Reno Total Depth 3660' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

Fill hole with sand to 3600' and cement with 5 sacks cement.

Bail hole to 230'. Set rock bridge from 230' to 220' and cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


 Conservation Division Agent