



15-055-20241-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1977

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Carl Bentley of Mack Oil Co. has this
date requested permission to plug the following described well:

Mr. Carl Bentley guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company

Complete Address: P.O. Box 400, Duncan, OK 79533

Lease Name: Mai Well No. 1

Location: C NE SW Sec. 14 Twp. 22 Rge. (E) (W) 29

County: Finney Total Depth 4820 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Carl Bentley was instructed to plug the well as follows:

Ran 2-3/8" tubing to 400'. Pumped 50 sacks cement from 400'
into surface casing at 250'. Pull 10 jts. of tubing & pump
15 sacks cement from 60' to surface of ground. Place 5 sacks
cement in rat hole. Pulled remainder of tubing from hole.

Very truly yours,

Frank Leonard
Conservation Division Agent