

15-145-30093-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 6 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Musgrove of Hellam Oil Co. has this  
date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Hellam Oil Co. Inc.

Complete Address: 337 Union Center Wichita, Kans.

Lease Name: Koehn Well No. 1

Location: N-SW-SW Sec. 21 Twp. 6 Rge. 17 (E)(W) X

County Pawnee Total Depth 4057 Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Musgrove was instructed to plug the well as follows:

Jet pits circulate hole with heavy mud, set cementing plug at 540 ft.,

and displace 25 sac cement thru drill pipe, heavy mud to 240 ft., set  
cementing plug and displace 20 sac cement thru drill pipe, heavy mud

to 40 ft., set cementing plug, 1/2 sac hulls and 15 sac cement, cementing

to base of cellar. Plug rat hole with two sac cement. Use Pump truck

Very truly yours,

Leo Messing  
Conservation Division Agent