



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Mobil has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corporation

Complete Address: Box 1934, Oklahoma City, Oklahoma

Lease Name: Harold Stevenson Well No. 1

Location: C NE NE Sec. 7 Twp. 22 Rge. 33 XX (E) (W)

County: Finney Total Depth 4810' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1028' circulated w/ cement. 5 1/2" to 4809' cemented.

Top perforations 4720' Plug bottom w/ 20 sacks cement.

Top of cement 4600' Mud 4600' to 800'

Spot 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Hulls ~ 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent