

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-20450-00-01
Spot: NWNWSWNW Sec/Twnshp/Rge: 34-31S-10E
3634 feet from S Section Line, 4985 feet from E Section Line
Lease Name: WALKER K Well #: 1
County: ELK Total Vertical Depth: 2400 feet

Operator License No.: 6129
Op Name: WALKER, KENNETH V.
Address: 140 RD 13
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2174		150 SX
SURF	4.5	524		85 SX

Well Type: SWD UIC Docket No: D20732.0 Date/Time to Plug:
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: KENNETH V WALKER Company: Phone: (620) 647-3406

Proposed Plugging Method: Plug: run one inch tubing to 2100 feet in hole: put 5 sacks of cement: at 1200 feet put 5 sacks of cement: at 550 feet cement to top: estimate 60 sacks of cement

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 01/24/2017 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 2010' gelled hole with 2 sacks and spotted 5 sack plug. Pulled up to 1200' and spotted 5 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 68 sacks of cement were used to plug this well. Well cut off and locaiton restored.

Perfs:

Top	Bot	Thru	Comments
2080	2090		

RECEIVED
KCC DIST # 3
FEB 01 2017
CHANUTE, KS
DS
KCC WICHITA
FEB 06 2017
RECEIVED

Remarks:
Plugged through: TBG

District: 03

Signed Duane A Sims
(TECHNICIAN)

INVOICED
FEB - 8 2017