

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-32132-00-01
Spot: SESENW Sec/Twnshp/Rge: 13-34S-13E
2952 feet from S Section Line, 2784 feet from E Section Line
Lease Name: HOLLANDSWORTH Well #: 3
County: MONTGOMERY Total Vertical Depth: 853 feet

Operator License No.: 9749

Op Name: MELANDER, CHRIS DBA CHRIS MELA

Address: 2256 CR 2500
CANEY, KS 67333

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	841		
PROD	3	845		100 SX
SURF	8.625	20		18 SX

Well Type: EOR

UIC Docket No: E31310.2

Date/Time to Plug: 09/14/2016 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: CHRIS MELANDER

Company:

Phone: (620) 289-4723

Proposed Plugging Method: Run 1" to Total Depth. Fill from Total depth to Surface with Portland Type 1 cement. Cut casing below GL. Restore location.

Plugging Proposal Received By: DUANE SIMS

WitnessType: PARTIAL

Date/Time Plugging Completed: 09/14/2016 2:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

KCC WICHITA

FEB 06 2017

RECEIVED

Ran 1" to 875' gelled hole and spotted 2 sack plug. Pulled up to 500' and spotted 2 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 12 sacks of cement were used to plug this well. Well has not been cut off as of January 18, 2017.

**RECEIVED
KCC DIST # 3**

FEB 01 2017

CHANUTE, KS


DS

Remarks: WELL WAS PLUGGED DUE TO OPERATOR RELEASING THE LEASE BACK TO LANDOWNER.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

Form CP-2/3

INVOICED

FEB - 8 2017