

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-32234-00-00
Spot: SESENW Sec/Twnshp/Rge: 13-34S-13E
3234 feet from S Section Line, 2881 feet from E Section Line
Lease Name: HOLLANDSWORTH Well #: 2
County: MONTGOMERY Total Vertical Depth: 1399 feet

Operator License No.: 9749
Op Name: MELANDER, CHRIS DBA CHRIS MELA
Address: 2256 CR 2500
CANEY, KS 67333

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.4	1399		140 SX
SURF	8.5	20		12 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: CHRIS MELANDER Company: _____ Phone: (620) 289-4723

Proposed Plugging Method: Remove tubing and pump. Run 1" tubing to bottom. Fill to surface with Portland type 1. Cut casing below GL. Restore Location.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2016 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 875' gelled hole and spotted 5 sack plug. Pulled up to 500' and spotted 5 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 35 sacks of cement were used to plug this well. Well has not been cut off as of January 18, 2017.

Perfs:

Top	Bot	Thru	Comments
802	812		

RECEIVED
KCC DIST # 3
FEB 01 2017
CHANUTE, KS
DS

KCC WICHITA
FEB 06 2017
RECEIVED

Remarks: WELL WAS PLUGGED DUE TO OPERATOR RELEASING THE LEASE BACK TO LANDOWNER.

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

INVOICED Form CP-2/3
--INVOICED

FEB - 8 2017