

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-21844-00-02  
Spot: SENE Sec/Twnshp/Rge: 1-29S-14E  
4180 feet from S Section Line, 165 feet from E Section Line  
Lease Name: DOCIA BATES Well #: 1  
County: WILSON Total Vertical Depth: 1105 feet

Operator License No.: 34697  
Op Name: WILSON COUNTY HOLDINGS LLC  
Address: 1135 N. 15TH ST.  
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1060		102 SX
SURF	5	40		12 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2016 8:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: FORREST D SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Tie onto well and squeeze cement until pressure starts to rise and shut well in holding pressure. Bleed pressure off the next day and top well off using 15ppg portland cement.

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/12/2016 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A one inch cement string was lowered to 1070 ft inside the 2.875". 33 sacks of cement were then pumped. Cement did not return to surface. The one inch was pulled and the cement allowed to set. Returned to the well the next day and the one inch cement string lowered to 780 ft where the cement was tagged. The well was then pumped full of cement with an additional 29 sacks. A total of 62 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED  
KCC DIST # 3  
JAN 31 2017  
CHANUTE, KS

AD

KCC WICHITA  
FEB 06 2017  
RECEIVED

Remarks:

Plugged through: CSG

District: 03

Signed

*Alan Dunning*

(TECHNICIAN)

Form CP-2/3

INVOICED

FEB - 8 2017